



IDECO 3000 HP Drilling Rig

MAST	DSI Cantilever 152' Clear Ht. Hook Load: 1,500,000# 8 X Sheaves 14 lines
SUBSTRUCTURE	DSI 30' Floor Ht. 24' Clear Total Loadbearing Capacity: 1,500,000# 760,000# set-back
DRAWWORKS	IDECO 3000E 3 X 752 GE Traction Motors (1,000HP/ea.) Baylor 7838 Brake System Depth Rating: 25,000' Line: 1-5/8"
ROTARY TABLE	VARCO 37-1/2" 2 X GE 752 Traction Motors
TDS	No
IRON ROUGH NECK	No
CATWALK	Yes
HOISTING SYSTEM	LTI Crown Block Assembly: 1,600,000# Sheaves: 7 X 60"; 1 X 72" API Rated: 850 tons
SWIVEL	No

TRAVELING BLOCK	750 ton American Block 14 lines
POWER PLANT	3 X 3512C CAT w/ 1750 Kw Generators
SCR / VFD	5 X 5 IEC I-drive M2200 SCR System
MUD PUMPS	3 X LTI Lewco 1600HP Mud Pumps 5600PSI
MUD TANKS	4 X Tanks Total Capacity: 2,000 Bbl.
SOLIDS CONTROL	3 X Derrick 48 Shale Shakers 1 X Desander/Desilter
WATER STORAGE	3 X tanks 1,500 Bbl. Total
FUEL STORAGE	16,000 gal.
BOP	No
BOP HANDLING SYSTEM	Yes – 30 ton

* Note some of the illustrated items may not be specified in exact terms and all items are subject to change.