



LTI 3000HP AC Drilling Rig (Constructed 2009/Upgraded Hook Load 2015)

MAST	<p>Cantilever</p> <p>156' Clear Ht.</p> <p>Hook Load: 1,700,00#</p> <p>14 lines</p>
SUBSTRUCTURE	<p>LR 1300</p> <p>38' Clear Floor Ht.</p> <p>Total Loadbearing Capacity: 1,700,000#</p>
DRAWWORKS	<p>LTI LDW 1500K</p> <p>Depth Rating: 25,000'</p> <p>Nominal HP Input: 4,500HP</p> <p>Line: 1-5/8"</p> <p>Auxiliary Brake System LTI</p>
ROTARY TABLE	<p>Table Opening: 37-1/2"</p> <p>Static Load Capacity: 650 tons</p>
TDS	LTI 750 ton Electric TDS
IRON ROUGH NECK	Canrig Torq-Matic 120 – 125
POWER CATWALK	Canrig Hydraulic Catwalk System
HOISTING SYSTEM	<p>LTI Crown Block Assembly: 1,700,000#</p> <p>Sheaves: 7 X 60"; 1X 72"</p> <p>API Rated: 850 tons</p>
SWIVEL	<p>Type L70</p> <p>Load Rating: 1,490,000#</p> <p>WP: 10,000PSI</p>

POWER PLANT	5 X Cat 3512C + Kato 1 X Cat Emergency Generator C15
MUD PUMPS	3 X LTI WH 1612 Mud Pumps 7500PSI
MUD TANKS	8 Tanks Total Capacity: 4,000Bbls.
SOLIDS CONTROL	3 X NOV Shale Shakers 1 X Mud Cleaner/1 X Desander/Desilter
WATER STORAGE	2 Tanks Total Capacity: 1,000Bbls
FUEL STORAGE	16,000 gal.
BOP	No
BOP HANDLING SYSTEM	Yes – 35 ton

* Note some of the illustrated items may not be specified in exact terms and all items are subject to change.